

STANDARD OPERATING PROCEDURE: SOP-P194-01

1. Scope & Regulatory Framework

Procedure Title: Standard Operating Procedure for Hydrocarbon Process Pump P-194

Asset Identifier: P-194 | Unit: Fluid Processing Train 2

Governance Version: v2.0 | Governance Status: Approved

Governing Regulations:

- OISD-STD-119: Process Piping & Machinery Operational Inspection Guidelines
- The Factories Act 1948 Section 21: Rotating machinery fencing & protective interlocking
- PESO Rule 33: Hydrocarbon Pressure Piping and Vessel statutory compliance

2. Pre-Start Verification Checklist

1. Verify suction line 194-A valve is 100% open and locked in open position.
2. Verify seal barrier fluid pressure is pressurized to 2.5 bar above suction pressure.
3. Verify lube oil reservoir contains ISO VG 46 turbine oil at minimum 65% glass level.
4. Confirm mechanical coupling safety cage is securely latched.
5. Confirm emergency stop push button is reset and control interlocks are healthy.

3. Normal Running & Stop Sequence

Start 55 kW driver and observe pressure build-up on PT-194 to 18.2 bar.

Gradually crack open discharge control valve V-194 until FT-194 indicates 140 m3/h flow.

In the event of vibration exceeding 7.1 mm/s RMS or temperature exceeding 95 deg C, automated trip initiates.